

MJP Electric and Construction, Inc.

(Chicago Metro) 15300 S. RT 59 STE#103 PLAINFIELD, IL 60586, TEL 815-254-9868

(Dallas Metro) 3100 Independence Pkwy, Suite #311, TEL 972 382 9942

BID PROPOSAL

1/28/2015

RE: Key Development Partners, Bolingbrook, IL

We are pleased to quote the Electrical Installation on the above referenced project as *Per Drawings: E1, E2, and SPI Dated 10-07-2014*

ELECTRICAL PRICE: \$17,500.00

Inclusions (Material and Labor for Following as Specified)

2-Light Poles (Poles, Fixtures and Bases supplied by other)
1-Pylon Sign (Sign and base by other)
9-Exterior Wall Fixtures
1-2" Conduit to From Demark to Phone Board per Plan Location
2-Exit/EM Combo Fixtures
2-Exterior EM heads with Remote Battery Packs
2-J boxes and 1" Conduit and Pull String for Sign from Store front to Panel "A"
Metering, Panels, and Disconnects Per Plans
2-Feeds to RTU's Per Plans with Roof top GFI's
Under Ground conduits and Cables per Plans to From Meter to Transformer Pad
Transformer Pad per Com Ed Requirements
Recp for Irrigation panel per Plans

Note ***

Panel "A" is a 200 amp MLO panel, but calls for a 400 amp sub breaker to be on spaces 37, 39, 41 which is not possible because buss rating is on specified to be 200amp. If you would like to accomplish this panel must be upgrade to a 400 amp MLO Panel. Price is substituting a to a 2 section 84 space feed through with 42 spaces in "a" and 42 spaces in "b".

Exclusions

Empty conduit's with pull string to D-Mark from Tele-Co Company Pedestal
Empty Primary conduits with pull strings from Com Ed Pedestal to Transformer Pad
Fixtures, Pylon Sign and Poles and Heads
Concrete and Hole for pole Bases
Concrete base and pylon sign.

We would like to thank you for the opportunity to quote this project. Please contact me via email at jpanici@mjpelectric.com or I can be reached at 815 474 2744 for any questions.

Sincerely,
Joseph Panici